

# Residential Septic Plan

100% EXPANSION AREA  
MINOR REGRADING OF  
EXISTING SOIL MAY BE  
NECESSARY

24" WIDE SEPTC TRENCHES 7' O.C.  
W/ 4" PERFORATED PIPE ENCASED  
IN GRAVEL - TOTAL LENGTH 625 FT.

APPROX. LIMIT OF SSDA

200 ft. FROM EDGE  
OF POND

750 GAL. PRECAST CONC. PUMP CHAMBER  
1500 GAL. PRECAST CONC. SEPTIC TANK

200 FT. DIRECT LINE  
OF DRAINAGE

**Proposed 5 Bedroom  
Residence**  
FF Elev. 220.33  
BF Elev. 210.33  
GF Elev. 210.00

C.B.  
GR.=191.7

S=3%  
PROPOSED DRIVEWAY

100' MIN. TO SSTS  
PROPOSED WELL

